

Turbo CF 80 Freon Refrigerated Ice Makers

2-- Turbo CF 80 freon refrigerated Ice makers rated at 40 tons each per 24 hour day. Includes a 300 ton FES screw package and Evapco Condenser complete set up for R-22, complete with a refrigerant receiver with all of the site columns, and isolation valves installed and capped . No starter. Can be divided into two seperate ice makers.

The ice makers are Turbo Mfg Co, the compressor unit is a FES screw package set up for r-22 refrigerant. There is an Evapco condenser with an additional glycol cooling circuit for the compressor. In addition is a refrigerant receiver with all of the site columns, and isolation valves installed and capped.

To put the system back in operation one would set the ice makers, add some take away screw conveyors, set the compressor unit which includes the system cooler, the suction accumulator protection and the liquid subcooler all pre packaged. Set the condenser and receiver and pipe between the color coded valves.

The compressor starter is not available, but I think the other starters are available.

The unit was very well maintained, they look to be in excellent condition. The ice maker units are turbo cfr 80's That is a remote refrigerant unit, thus the screw compressor. The compressor was upsized a few years ago with a new compressor, bigger then original and a bigger motor, 300 vs 250 hp. So the critical compressor is newer by 10 - 12 years then the original package.

All of the feeds to the ice maker look very clean and there is no obvious signs of leaks or problems.

